


NOTES:

1. BLACK SAND SLURRY SEAL SHALL BE EXTENDED 12" BEYOND THE A.C. PAVEMENT REPLACEMENT LIMIT.
2. GLASGRID®8512 PAVEMENT REINFORCEMENT GRID (OR APPROVED EQUAL) SHALL BE INSTALLED (FULL WIDTH & LENGTH OF TRENCH) IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATION FOR TRENCH IN STREETS LISTED IN APPENDIX C.
3. A.C. PAVEMENT REPLACEMENT SHALL BE FULL DEPTH A.C. WITH THICKNESS PER CITY REQUIREMENT. SEE "TRENCH PAVEMENT THICKNESS REQUIREMENTS" (APPENDIX C) FOR REQUIREMENTS OF A PARTICULAR STREET.
4. THE 6" BENCH SECTION FOR A.C. SHALL BE CUT AND REMOVED IMMEDIATELY PRIOR TO FINISH PAVING OPERATIONS.
5. FOR WATER MAINS AND LATERALS, BEDDING SHALL BE SAND, EXTENDING 12" OVER TOP OF PIPE.



DRAWN BY: M. LEE

CHECKED BY: S. THACH

APPROVED BY: T. SUPAN

DATE: DECEMBER 2005

TRENCH BACKFILL AND  
PAVEMENT REPLACEMENT

ST-19

CITY OF SANTA CLARA

PAGE: 19