



NOTES:

1. AFTER THE COBBLESTONE HAS BEEN SET INTO THE MORTAR, THE EXCESSIVE MORTAR IN BETWEEN THE JOINTS OF THE COBBLESTONES SHALL BE CAREFULLY REMOVED AND RAKED IN A SMOOTH JOINT (NO PROTRUSION OF MORTAR WILL BE ALLOWED).
2. CLEAN MORTAR FROM VISIBLE PORTIONS OF COBBLESTONES AFTER INSTALLATION.



DRAWN BY:	K. TRAN
CHECKED BY:	F. AMIN
APPROVED BY:	F. AMIN
DATE:	JANUARY 2016

<b>MEDIAN COBBLESTONE INSTALLATION</b>
CITY OF SANTA CLARA

<b>ST-13A</b>
PAGE: 13A