

Building Division: 408-615-2440 Email: Building@santaclaraca.gov Permit Center: 408-615-2420

Email: <u>PermitCenter@santaclaraca.gov</u>

Automated Inspection Scheduling System: 408-615-2400

2022 CALIFORNIA BUILDING CODE - SECTIONS 11B-208, 11B-501 & 11B-502 GENERAL REQUIREMENTS FOR ACCESSIBLE PARKING

NUMBER OF PARKING SPACES (CBC Table 11B-208.2)

| Total Number of Parking Spaces Provided in Parking Facility | Minimum Number of Required Accessible Parking Spaces |
|--|---|
| 1-25 | 1 |
| 26-50 | 2 |
| 51-75 | 3 |
| 76-100 | 4 |
| 101-150 | 5 |
| 151-200 | 6 |
| 201-300 | 7 |
| 301-400 | 8 |
| 401-500 | 9 |
| 501-1000 | 2% of total |
| 1001 & Over | 20+1 for each 100, or fraction thereof over 1000 |

Notes:

- a. **Hospital outpatient facilities**: required accessible spaces shall be 10% of the total spaces, per 11B-208.2.1.
- b. Rehabilitation facilities and outpatient physical therapy facilities (specializing in treating conditions that affect mobility): required accessible spaces shall be 20% of the total spaces, per 11B-208.2.2.
- c. One (1)-van sized accessible space for every 6 accessible parking spaces, per CBC 11B-208.2.4.

* PARKING SPACE SIZE AND LAYOUT




Figure: Single Accessible Parking Stall



* Passenger Drop-Off and Loading Zone Access Aisle

When Required

- a. Passenger Drop-Off & Loading Zone: Provide at least one accessible passenger drop-off and loading zone complying with CBC 11B-503 in every continuous 100 linear feet of dropoff and loadingzone space, per 11B-209.2.1.
- b. Valet Parking: Parking facilities that provide valet parking services shall provide at least one accessible passenger drop-off and loading zone complying with CBC 11B-503 at vehicle drop-off andvehicle pick-up areas, per 11B-209.4.
- c. **Mechanical Access Parking Garages:** Provide at least one accessible passenger dropoff and loading zone complying with CBC 11B-503 at vehicle drop-off and vehicle pick-up areas, per 11B-209.5.

General Requirements: (CBC 11B-503)

- a. Vehicle Pull-up Space: 8'-0" wide minimum x 20'-0" long minimum.
- b. Access Aisle: 5'-0" wide minimum x 20'-0" long minimum adjacent and parallel to the vehicle pull-upspace. Access aisle shall adjoin an accessible route and shall not overlap the vehicular way.
- c. **Marking:** Access aisle shall be marked with a painted borderline around their perimeter. The areawithin the borderlines shall be marked with hatched lines a maximum of 36" on center in a color contrasting with that of the aisle surface.
- d. Slope: Max 1:48 in all directions. Also, detectable warnings shall not be permitted, per 11B-503.4.




Figure: Passenger Drop-Off and Loading Zone Access Aisle